

Please type a plus (+) sign inside this box

Office: U.S. DEPARTMENT OF COMMERCE

Under the Paperwork Reduction Act of 1995, no persons are required to respond to a collection of information unless it displays a valid OMB control no.

PTO/SB/05 REV 1 (12/97)
Approved for use through 09/30/2000. omb 0651-0032
Patent and Trademark

**UTILITY
PATENT APPLICATION
TRANSMITTAL**

Only for new nonprovisional applications under 37 CFR 1.53(b)

Attorney Docket No. 10990265-1

First Inventor or Application Identifier:

DAVID SCOTT TAUBMAN

Title

APPARATUS FOR AND METHOD OF SNR SCALABLE QUANTIZATION
BIT-PLANE CODING

Express Mail Label No.

EL518741559US

APPLICATION ELEMENTS

See MPEP chapter 600 concerning utility patent application contents.

ADDRESS TO:

Assistant Commissioner for Patents
Box Patent Application
Washington, D.C. 20231

1. ☒ Fee Transmittal Form
(Submit an original, and a duplicate for fee processing)
2. ☒ Specification [Total Pages 23]
(preferred arrangement set forth below)
- Descriptive title of the Invention
 - Cross References to Related Applications
 - Statement Regarding Fed sponsored R & D
 - Reference to Microfiche Appendix
 - Background of the Invention
 - Brief Summary of the Invention

6. ☐ Microfiche Computer Program (Appendix)
7. ☐ Nucleotide and/or Amino Acid Sequence Submission
(if applicable, all necessary)
- a. ☐ Computer Readable Copy
 - b. ☐ Paper Copy (identical to computer copy)
 - c. ☐ Statement Verifying identity

- Brief Description of the Drawings (if filed)

- Detailed Description
- Claim(s)
- Abstract of the Disclosure

3. ☒ Drawing(s) (35 USC) 113) [Total Sheets 16]

4. ☒ Oath or Declaration [Total Pages 3]

- a. ☒ Newly executed (original or copy)
- b. ☐ Copy from a prior application (37 CFR 1.63(d))
(for continuation/divisional with Box 17 completed)
[Note Box 5 below]
- i. ☐ DELETION OF INVENTOR(S)
Signed statement attached in the prior application, see
37 CFR 1.63(d)(2) and 1.33(b).

5. Incorporation by Reference (useable if Box 4b is checked)
The entire disclosure of the prior application, from which a copy
of the oath or declaration is supplied under Box 4b, is considered
as being part of the disclosure of the accompanying application
and is hereby incorporated by reference therein.

ACCOMPANYING APPLICATION PARTS

8. ☐ Assignment Papers (cover sheet & document(s))
9. ☐ 37 CFR 3.73(b) Statement
(when there is an assignee) ☐ Power of Attorney
10. ☐ English Translation Document (if applicable)
11. ☒ Information Disclosure Statement (IDS)/PTO-1449 3 Copies of IDS Citations
12. ☐ Preliminary Amendment
13. 2 Return Receipt Postcard (MPEP 503)
(Should be specifically itemized)
14. ☐ Small Entity ☐ Statement filed in prior application,
Statement(s) Status still proper and desired
15. ☐ Certified Copy of Priority Document(s)
(if foreign priority is claimed)
16. Other: _____

17. If a CONTINUING APPLICATION, check appropriate box and supply the requisite information:

☐ Continuation ☐ Divisional ☐ Continuation-in-part (CIP) of prior application No.: _____ / _____
Prior application information: Examiner _____ Group/Art Unit _____

18. CORRESPONDENCE ADDRESS

☐ Customer Number or Bar Code Label _____ or ☒ Correspondence address below

(Insert Customer No. or Attach bar code label here)

NAME

ATTN: MARC P. SCHUYLER

HEWLETT PACKARD COMPANY

ADDRESS

IP ADMINISTRATION

POST OFFICE BOX 272400

CITY

FORT COLLINS

STATE

COLORADO

ZIP CODE

80527-2400

COUNTRY

USA

TELEPHONE

(650) 857-3359

FAX

(650) 852-8063

Name (Print/Type)

LAWRENCE A. MAXHAM

Registration No. (Attorney/Agent)

24,483

Signature

Lawrence A. Maxham

Date

21 March 2000

-1-

APPARATUS FOR AND METHOD OF SNR SCALABLE QUAD-TREE BIT-PLANE CODING

BACKGROUND OF THE INVENTION

5 1. Field of Invention

The present invention relates generally to the field of computer coding and pertains more particularly to coding the bit-planes of an array of numbers.

2. Discussion of the Prior Art

With the advent of the computer and the Internet, man is living increasingly in an
10 information age. The storage and transmission of information or data has taken on a
heightened importance. Unfortunately, storage space and transmission bandwidth are not
unlimited. Modern computer systems have become increasingly graphics intensive.
Dedicated special purpose memories and hardware have been developed to meet this need.
New and improved graphics file formats and communication protocols are being developed
15 as well. As graphics technologies and products become more prevalent in consumer areas,
slim profit margins are demanding the utmost efficiencies. Compression is necessary to
achieve efficiency in database representation to conserve disk storage, system memory, cache
memory, and special purpose memories. Additional savings can be achieved by conserving
bus bandwidths, which becomes more critical with unified computer architectures where
20 graphics and system memory are one and the same.

Data compression is often used to reduce the cost of storing large data files on
computers as well as to reduce the time for transmitting large data files between computers.
Several compression techniques exist. One technique is to transform the data from its
original form into a second form which is easier to manipulate. In the so-called "transform

-2-

methods" data is transformed into coefficients that represent the data in a frequency domain. Coefficients may be quantized without significantly affecting the quality of data that is reconstructed. This is a form of lossy compression. Lossy compression refers to compression with some effect on the rendered output. Redundancy in the coefficients may then be reduced or eliminated without affecting the quality of the reconstructed data. This is a form of lossless compression. Lossless compression refers to compression with no effect on the rendered output.

One well known class of transforms are Wavelet transforms. The Wavelet transforms may be used to perform subband decomposition and produce coefficients that describe the data in a hierarchical multiscale representation. Wavelet transforms have proven useful for the compression of images and the analysis of signals. They have been proposed as the transform for the emerging JPEG-2000 standard.

Among the advantages of the Wavelet transforms is that the transform coefficients can be ordered in a hierarchical structure and transmitted in an "embedded bitstream." The embedded bitstream has a property whereby prefixes of the bitstream yield a continuum of lower rate descriptions of the data at the highest possible levels of quality. If the embedded bitstream is truncated during transmission of image data, for instance, the information already transmitted will allow an entire image to be reconstructed. The quality of the reconstructed image is dependent upon the amount of information transmitted. As additional information is transmitted, the quality of the reconstructed image is improved. If the entire bitstream is transmitted without truncation, a lossless or near-lossless image can be reconstructed. If an embedded bitstream is truncated, a complete image of reduced quality can be reconstructed from the transmitted bits. In contrast, truncation of a non-embedded transmission might only allow several rows of an image to be reconstructed.

-3-

The transmission just described is often referred to as a progressive-by-quality or SNR (signal to noise ratio) scalable image transmission. The coefficients are converted to binary and described by bit-planes. The most significant coefficient bits, that is, the coefficient bits conveying the most important information, are transmitted first. The lesser significant
5 coefficient bits are then transmitted in order of decreasing importance with the least significant coefficient bits being transmitted last.

Another type of transmission is often referred to as progressive-by-resolution transmission. The progressive-by-resolution transmission involves ordering the coefficients according to different levels of image resolution. The different levels are identified by
10 markers in the embedded bitstream. A computer may use the markers to parse the bitstream and transmit the data for the coefficients corresponding to a resolution that is specified by the receiving computer. The receiving computer can then reconstruct an image according to the specified resolution.

A number of coding algorithms have been proposed for ordering the description of the
15 transform coefficients such that the retained number of bits of the description can produce the best quality image. For example, algorithms have been proposed by Shapiro, known as the "Zerotree" algorithm, and an improvement thereon by Said-Pearlman, known as the "SPIHT" algorithm, among others. However, there are a number of problems associated with the Zerotree based algorithms. Among these problems is that Zerotree coders rely on the use of a
20 complex arrangement of lists and pointers. Further, the Zerotree coders minimize image distortion only at bit-plane boundaries. As long as the transmission is truncated at a bit-plane boundary, the image distortion will be minimized. However, if a transmission is truncated at a point other than a bit-plane boundary, the image distortion will not be minimized.

-4-

A definite need exists for a system having an ability to meet the efficiency requirements of graphics intensive computer systems. In particular, a need exists for a system which is capable of ordering the description of the transform coefficients in a simple and fast manner. Ideally, such a system would have a lower cost and a higher productivity than conventional systems. With a system of this type, system performance can be enhanced. A primary purpose of the present invention is to solve this need and provide further, related advantages.

SUMMARY OF THE INVENTION

An apparatus for and a method of coding the bit-planes of an array of numbers is disclosed. The values in the array of numbers are converted to binary. The binary values are truncated to a predetermined level of accuracy. The number of bit-planes is determined based on the largest absolute value. A tree structured description of the array is generated based on a modified quad-tree coding technique. An SNR scalable encoding of the significance information for each bit-plane is generated by describing new branches and leaves of the tree corresponding to each bit-plane in a bottom-up-depth-first manner. An encoding of refinement information for each bit-plane is generated. A SNR scalable description of the array is generated by concatenating the encoding of the significance information and the refinement information generated for each bit-plane.

BRIEF DESCRIPTION OF THE DRAWING

The above and other objects and advantages of the present invention will be more readily appreciated from the following detailed description when read in conjunction with the accompanying drawing, wherein:

-5-

FIG. 1 is a block diagram of a coding system according to one embodiment of the present invention;

FIG. 2 is a graphical representation of a hierarchical subband decomposition of a sixteen pixel by sixteen pixel image;

5 FIG. 3 is an example of a square array representing subband SB8 from FIG. 2;

FIG. 4 is a table illustrating the binary conversion of the decimal values of the non-zero coefficients from FIG. 3;

FIG. 5A is an example of a square array of significance information for the highest bit-plane of the coefficients from FIG. 3;

10 FIG. 5B is a quad-tree description of the square array of significance information of FIG. 5A;

FIG. 5C is a table illustrating the encoding of the significance information and the refinement information for FIGS. 5A and 5B;

15 FIG. 6A is an example of a square array of significance information for the second highest bit-plane of the coefficients from FIG. 3;

FIG. 6B is a quad-tree description of the square array of significance information of FIG. 6A;

FIG. 6C is a table illustrating the encoding of the significance information and the refinement information for FIGS. 6A and 6B;

20 FIG. 7A is an example of a square array of significance information for the third highest bit-plane of the coefficients from FIG. 3;

FIG. 7B is a quad-tree description of the square array of significance information of FIG. 7A;

-6-

FIG. 7C is a table illustrating the encoding of the significance information and the refinement information for FIGS. 7A and 7B;

FIG. 8A is an example of a square array of significance information for the lowest bit-plane of the coefficients from FIG. 3;

5 FIG. 8B is a quad-tree description of the square array of significance information of FIG. 8A; and

FIG. 8C is a table illustrating the encoding of the significance information and the refinement information for FIGS. 8A and 8B.

10 DETAILED DESCRIPTION OF THE PREFERRED EMBODIMENTS

Turning first to FIG. 1, a block diagram of a coding system 10 according to one embodiment of the present invention is shown. The coding system 10 operates on an input image 12 which is decomposed using a standard sampling filter 14. Under a Wavelet transform, the filter 14 decomposes the image into four frequency subbands which will be
15 further described below. The output of the filter 14 is termed a Wavelet transform 16 which is processed by an encoder 18 to generate a compressed image 20. The encoder 18 efficiently generates the compressed image 20 using a modified quad-tree coding technique described below. The compressed image 20 may be decompressed using a decoder 22. The decoder 22 similarly utilizes an inverse of the modified quad-tree coding technique to produce an output
20 image 24.

FIG. 2 shows a graphical representation of a hierarchical subband decomposition of a sixteen pixel by sixteen pixel image. A Wavelet transform may be used to perform the subband decomposition. The filter 14 of FIG. 1 is such an example. At a first level of decomposition, image data, that is, luminance or chrominance data of an image, is filtered by

-7-

high pass and low pass filters, both horizontally and vertically. Then each of the resulting bands is subsampled by a factor of two, both horizontally and vertically. At the first level, the resulting subbands are as follows: a low pass horizontal, low pass vertical subband; a high pass horizontal, low pass vertical subband (SB9); a high pass horizontal, high pass vertical subband (SB8); and a low pass horizontal, high pass vertical subband (SB7). Each subband is one-quarter the size of the original image. In this case, at the first level, each subband will contain sixty-four coefficients arranged in a square array or matrix pattern.

Each additional decomposition is performed on the low pass horizontal, low pass vertical subband generated at the previous level of decomposition. The results are the SB4-SB6 subbands as shown and a new low-low band. In this case, at the second level, each subband will contain sixteen coefficients arranged in a square array. Further, the third decomposition would be performed on the new low-low band. The results are the SB0-SB3 subbands as shown. In this case, at the third level, each subband will contain four coefficients arranged in a square array. Three levels of decomposition are performed to produce the three-level subband decomposition shown. The resulting array of coefficients in this case is sixteen by sixteen having 256 entries. In actual practice, the number of levels of decomposition will depend on the image size with the larger the image the larger the number of decompositions and the larger the array of coefficients. The resulting array quickly becomes unwieldy for manual analysis.

The coarsest frequency information may be found in the lowest frequency subband SB0. The finest frequency information may be found in the highest frequency subband SB8. Parent-child dependencies are shown with the arrows pointing from the subband of the parent nodes to the subband of the child nodes. In a Wavelet transform, the magnitude of the coefficients become smaller as the frequency increases.

-8-

With reference to FIG. 3, an example of a square array representing subband SB8 from FIG. 2 is shown. The square array is filled with example coefficients and the rows and columns are labeled 1-8 from top to bottom and from left to right, respectively. In general, a coefficient will be represented as c_{ij} , where i is the row and j is the column. For example, coefficient $c_{1,4}$ is shown to have a value of 6 in the array. Upon review, one will realize that many of the entries have zero values. This is simply for convenience and will not necessarily be the case. The method below will be illustrated with respect to this square array, but one of ordinary skill will realize that the method can be expanded to any size square or rectangular array as necessary. Rectangular arrays are handled by extending the rows and columns with zero entries until a square array is obtained.

Quad-tree coding is a well known technique for generating a tree structured description of a square array having binary entries. The tree is described from the root at the top to the leaves at the bottom. At depth one or the root, there is only one node. The root node corresponds to the whole square array. From depth one down, the tree repetitively splits each node into four nodes at each successively lower depth. So, at depth two, there are four nodes. At depth three, there are four, eight, twelve, or sixteen nodes depending on whether or not each node at depth two split. Not every node will split at the next depth. This splitting continues until the description is complete. The size and shape of the tree will depend in part on both the size of the square array and the values of its entries. Except for the root, these nodes are either branches or leaves. Branches correspond to four equal sized row-column aligned quadrants or sub-blocks of the square array. Branches may also be referred to as internal nodes. Only those nodes corresponding to sub-blocks containing at least one non-zero entry have branches. Leaves correspond to sub-blocks that have all zero entries in the square array or, at the lowest depth, to sub-blocks of individual entries of the square array.

-9-

The lowest level leaves are labeled with the values of their corresponding array entries. The tree is typically described in a depth first fashion, starting from the root, by specifying whether the new node is a branch or a leaf.

One of ordinary skill in the art will realize that computers generally operate in binary.

5 As a result, decimal numbers have to be converted to binary. In general, the binary representation of a decimal number will take the form of $b^{m-1}b^{m-2}...b^nb^{n-1}...b^1b^0.b^{-1}b^{-2}...$ where each bit b is either one or zero. For example, the decimal number 10 converts to 1010 in binary ($b^3b^2b^1b^0$). In this case, m is equal to four because the binary representation has four bits ($4-1=3$). This represents full precision. If one did not need full precision, some of the bits could be ignored. For example, say one was limited to bits b^3 and b^2 in this case, still one would know that the decimal number was 8, 9, 10, or 11. In certain applications this may be enough precision. In return for less precision, the number of bits was cut in half in this case.

FIG. 4 shows a table illustrating the binary conversion of the decimal values of the non-zero coefficients from FIG. 3. One of ordinary skill will realize that for a full conversion, the sign will also need to be converted using the binary alphabet. This has been omitted for convenience. Each number has been converted using the number of bits needed for conversion of the maximum coefficient. In this case, coefficient $c_{1,1}$ has the maximum absolute value and requires four bits. As a result, even though coefficient $c_{4,2}$ only requires one bit, it is shown by way of four bits with leading zeros. Implicit in the illustration is that the precision was cut off at the decimal place. In general, the precision could be cut off at any bit position on either side of the decimal point. Zero bits greater than b^3 and less than b^0 have been ignored for convenience.

Taken together across the binary conversions, the bits at a given precision are called bit-planes. For example, the bits for b^3 are grouped into bit-plane three. Quad-tree coding for

-10-

generating a tree structured description of a square array having binary entries is applied to these bit-planes. The tree, represented by T_n where n is the number of the bit-plane, describes significance information as to which coefficients are significant relative to a particular bit-plane. The bit-planes are considered from highest to lowest. The significance information for a coefficient c_{ij} is represented by $s^n(c_{ij})$. A coefficient is said to be significant, that is, $s^n(c_{ij}) = 1$, at a particular bit-plane n if one of two conditions exist. First, if the coefficient has a value of one for the first time at that bit-plane, that is, the coefficient had leading zeros in all of the higher bit-planes $m-1$ through $n+1$. Second, if the coefficient had a value of one in any of the higher bit-planes, that is, the coefficient remains significant at all bit-planes below its initial significance. Otherwise, the coefficient c_{ij} is insignificant, that is, $s^n(c_{ij}) = 0$.

From the definition of significance it follows that once a coefficient becomes significant at a particular bit-plane it remains significant at all lower bit-planes. This means that for all bit-planes n , T_{n-1} , the quad-tree description of the significance information for bit-plane $n-1$, can be obtained by adding branches and leaves to the leaves corresponding to zero regions, that is, zero-labeled leaves, of T_{n-1} . In this sense, T_{n-1} is a refinement of T_n . The encoding of the manner in which T_n should be refined to obtain T_{n-1} is represented by Δ_n . The sign of the corresponding coefficient is encoded with the first significant bit for that coefficient using a one to represent a negative sign and a zero to represent a positive sign. At the highest bit-plane $m-1$, the significance information corresponds to the values of the coefficients for that bit-plane. For each bit-plane below the highest bit-plane, the values of the coefficients which became significant at higher bit-planes constitute refinement information and the encoding of this information is represented by R_n .

An SNR scalable bit-stream for a square array of coefficients is obtained by concatenating the significance information Δ_n and the refinement information R_n in the order

-11-

$$\Delta_{m-1} R_{m-1} \Delta_{m-2} R_{m-2} \dots \Delta_n R_n \Delta_{n-1} R_{n-1} \dots \Delta_1 R_1 \Delta_0 R_0 \cdot \Delta_1 R_1 \Delta_2 R_2 \dots \quad (1)$$

where R_{m-1} is always an empty set. This order is valuable because it allows some image to be generated even if the transmission is truncated during the transfer of the bit-stream. For best application of the quad-tree technique to bit-plane coding, attention should be paid to the manner in which a higher tree T_n is refined to obtain a lower tree T_{n-1} , the description of which constitutes Δ_{n-1} . The order of the description can have a significant effect on the smoothness of the distortion rate behavior of the final SNR scalable bit-stream. The refinement of T_n should be guided by what shall be called the embedding principle, that is, all bit-plane information should be described in order of decreasing expected distortion reduction per expected bit of description. Based on this principle, it can be shown that the result is that the significance tree should be described in a bottom-up-depth-first fashion. This means that in encoding the refinement of T_n into T_{n-1} , the new values of the maximum depth zero-labeled leaves of T_n are described first (including the signs of the newly significant coefficients). Then each new sub-tree, having new branches and leaves, growing out of each shallower zero-labeled leaf of T_n is described in a depth-first fashion. The shallower zero-labeled leaves of T_n are processed in order of decreasing depth. This procedure will be illustrated below with respect to the example of FIG. 3.

FIG. 5A shows an example of a square array of significance information $s^n(c_{i,j})$ for the highest bit-plane of the coefficients from FIG. 3. Recall from above that at the highest bit-plane, the significance information corresponds to the values of the coefficients for that bit-plane. So, in this example $s^3(c_{i,j})$ is equal to $b^3_{i,j}$. Because of this, all of the relevant information is contained in the encoding of the significance information Δ_3 and there is no refinement information R_3 for the highest bit-plane. A quad-tree description of the square array of significance information of FIG. 5A is shown in FIG. 5B. The resulting tree is of

-12-

depth four with some of the leaves at each of the depths two, three, and four. The tree is formed by examining the significance information at various depths. At depth one, the significance information is taken as a whole and is examined to determine if any of the entries are significant. In this case, both $s^3(c_{1,1})$ and $s^3(c_{4,3})$ are one indicating that $c_{1,1}$ and $c_{4,3}$ are significant. As a result, the root or node 26 is labeled with a one. At depth two, the significance information is broken into four quadrants and each quadrant is examined to determine if any of the entries in that quadrant are significant. In this case, the upper left quadrant has significant entries. As a result, node 28 is labeled with a one and nodes 30-34 are labeled with a zero. At depth three, each significant quadrant from depth two is broken into four sub-quadrants and each sub-quadrant is examined to determine if any of the entries are significant. In this case, the upper left sub-quadrant and the lower right sub-quadrant have significant entries. As a result, nodes 36 and 42 are labeled with a one and nodes 38 and 40 are labeled with a zero. At depth four, each significant sub-quadrant from depth three is broken down into four sub-sub-quadrants and each sub-sub-quadrant is examined to determine if any of the entries are significant. In this case, $s^3(c_{1,1})$, the upper left sub-sub-quadrant of the upper left sub-quadrant, and $s^3(c_{4,3})$, the lower left sub-sub-quadrant of the lower right sub-quadrant, are significant. As a result, nodes 44 and 72 are labeled with a one and nodes 46-50, 68, 70 and 74 are labeled with a zero. No further division of the significance information is possible, so the tree is complete. The final tree has root node 26, branch nodes 28, 36, and 42, and leaf nodes 30-34, 38, 40, 44-50, and 68-74. The positive sign [+] of $c_{1,1}$ has been noted under node 44 and the negative sign [-] of $c_{4,3}$ has been noted under node 72 as reminders to code the signs accordingly before coding nodes 44 and 72 themselves.

-13-

In FIG. 5C a table illustrating the encoding of the significance information and the refinement information for FIGS. 5A and 5B is shown. Recall from above that the significance tree T_n should be described in a bottom-up-depth-first fashion. Realize also that for the highest bit-plane $m-1$ the entire tree must be described. For convenience, the tree is described from left to right as drawn. Once described, a node is not redescribed. For instance, the root is only described once but is connected ultimately to all of the leaves. In this case, the order of the description is 26, 28, 36, 44-50, 38-42, 68-74, and 30-34. The resulting encoding of significance information Δ_3 is shown in the table. Remember that the sign of the corresponding coefficient is encoded with the first significant bit for that coefficient. Here, for example, the binary values of the positive and negative signs have been shown in square brackets for ease of identification, but no such bracket would be transmitted. Recall further from above that R_{m-1} is always an empty set. So, R_3 is an empty set in this example. Accordingly, after encoding of the highest bit-plane of the coefficients from FIG. 3, the SNR scalable bit-stream consists of $\Delta_3 R_3$ where R_3 is an empty set.

With reference to FIG. 6A, there is shown an example of a square array of significance information for the second highest bit-plane of the coefficients from FIG. 3. Recall from above that the coefficient remains significant at all bit-planes below its initial significance. So, $s^2(c_{1,1})$ and $s^2(c_{4,3})$ are one because $s^3(c_{1,1})$ and $s^3(c_{4,3})$, respectively, were one. In addition, newly significant at this bit-plane is $s^2(c_{1,4})$ because bit b^2 for coefficient $c_{1,4}$ is significant. A quad-tree description of the square array of significance information of FIG. 6A is shown in FIG. 6B. The resulting tree is still of depth four with most of the leaves at depth four, one of the leaves at depth three, and three of the leaves at depth two. The tree is formed by examining the significance information at the same depths as FIG. 5B above. At depth one, the significance information is the same as FIG. 5B. As a result, the root is labeled

-14-

with a one. At depth two, the significance information is the same as FIG. 5B. As a result, node 28 is labeled with a one and nodes 30-34 are labeled with a zero. At depth three, the significance information is the same as FIG. 5B with one addition. In this case, the upper right sub-quadrant also has a significant entry. As a result, nodes 36, 38, and 42 are labeled with a one and node 40 is labeled with a zero. At depth four, the upper right sub-quadrant from depth three is broken into four sub-sub-quadrants and each sub-sub-quadrant is examined to determine if any of the entries are significant. In this case, $s^2(c_{1,4})$, the upper right sub-sub-quadrant of the upper right sub-quadrant, is one. As a result, nodes 44, 54, and 72 are labeled with a one and nodes 46-52, 56, 58, 68, 70, and 74 are labeled with a zero. The final tree has root node 26, branch nodes 28, 36, 38, and 42, and leaf nodes 46-50, 52, 56, 58, 68, 70, 74, 40, and 30-34. The values for bits b^2 for coefficients $c_{1,1}$ and $c_{4,3}$ have been noted under nodes 44 and 72, respectively, for future reference when coding the refinement information.

Turning now to FIG. 6C, a table illustrating the encoding of the significance information and the refinement information for FIGS. 6A and 6B is shown. Because the coefficient remains significant at all bit-planes below its initial significance, the nodes of the tree that are labeled with a one will remain a one. As a result, below the highest bit-plane only the zero labeled nodes of the next higher tree are of interest. The other nodes can be ignored because they are known and have been described previously. In this case, only nodes 46-50, 68, 70, 74, 38, 40 and 30-34 of FIG. 5B are of interest for coding the new status of the leaf nodes of the tree of FIG. 6B. Describing the significance information from left to right and in a bottom-up-depth-first fashion, nodes 46-50 remain unchanged. Nodes 68, 70, and 74 also remain unchanged. Moving up to depth three, node 38 changes to being significant, as a result, nodes 52-58 must be described for the first time. Also, node 40 remains unchanged.

-15-

Moving up to depth two, nodes 30-34 remain unchanged. The resulting order of the description is 46-50, 68, 70, 74, 38, 52-58, 40, and 30-34. The resulting encoding of the new status of these nodes Δ_2 is shown in the table. Recall from above that for each bit-plane below the highest bit-plane, the values of the coefficients which became significant at higher bit-planes are refinement information and its encoding is represented by R_n . For convenience, the refinement information is described from left to right. In this case, the values for bits b^2 for coefficients $c_{1,1}$ and $c_{4,3}$ make up refinement information R_2 as shown in the table. Accordingly, after encoding of the two highest bit-planes of the coefficients from FIG. 3, the SNR scalable bit-stream consists of $\Delta_3 R_3 \Delta_2 R_2$.

FIG. 7A shows an example of a square array of significance information for the third highest bit-plane of the coefficients from FIG. 3. In addition to the coefficients that remain significant from above, newly significant at this bit-plane is $c_{3,2}$ because bit b^1 for coefficient $c_{3,2}$ is one and all higher bits are zero. A quad-tree description of the square array of significance information of FIG. 7A is shown in FIG. 7B. The resulting tree is still of depth four with most of the leaves at that depth and three of the leaves at depth two. At depths one and two, the significance information is the same as FIG. 6B. At depth three, the significance information is the same as FIG. 6B with one addition. In this case, the lower left sub-quadrant also has a significant entry. As a result, nodes 36-42 are labeled with a one. At depth four, the lower left sub-quadrant from depth three is broken into four sub-sub-quadrants and each sub-sub-quadrant is examined to determine if any of the entries are significant. In this case, $s^1(c_{3,2})$, the upper right sub-sub-quadrant of the lower left sub-quadrant, is one. As a result, nodes 44, 54, 62, and 72 are labeled with a one and nodes 46-52, 56-60, 64-70, and 74 are labeled with a zero. The final tree has root node 26, branch nodes 28 and 36-42, and leaf nodes 44-74 and 30-34. As above, the values for bits b^1 for coefficients $c_{1,1}$, $c_{1,4}$, and $c_{4,3}$ have

-16-

been noted under nodes 44, 54, and 72, respectively, for future reference when coding the refinement information.

Turning now to FIG. 7C, a table illustrating the encoding of the significance information and the refinement information for FIGS. 7A and 7B is shown. Recall from above that below the highest bit-plane only the zero labeled nodes of the next higher tree are of interest. In this case, only nodes 46-52, 56, 58, 68, 70, 74, 40, and 30-34 of FIG. 6B are of interest for coding significance information for FIG. 7B. Describing the significance information from left to right and in a bottom-up-depth-first fashion, nodes 46-52, 56, 58, 68, 70, and 74 remain unchanged. Moving up to depth three, node 40 changes to being significant, as a result, nodes 60-66 must be described for the first time. Moving up to depth two, nodes 30-34 remain unchanged. The resulting order of the description is 46-52, 56, 58, 68, 70, 74, 40, 60-66, and 30-34. The resulting significance information Δ_l are shown in the table. Because for each bit-plane below the highest bit-plane, the values of the coefficients which became significant at higher bit-planes are encoded as refinement information, in this case, the values for bits b^l for coefficients $c_{1,1}$, $c_{1,4}$, and $c_{4,3}$ make up the refinement information R_l as shown in the table. Accordingly, after encoding of the three highest bit-planes of the coefficients from FIG. 3, the SNR scalable bit-stream consists of $\Delta_3 R_3 \Delta_2 R_2 \Delta_l R_l$.

FIG. 8A shows an example of a square array of significance information for the lowest bit-plane of the coefficients from FIG. 3. In addition to the coefficients that remain significant from above, newly significant at this bit-plane is $s^0(c_{4,2})$ because bit b^0 for coefficient $c_{4,2}$ is one. A quad-tree description of the square array of significance information of FIG. 8A is shown in FIG. 8B. The resulting tree is still of depth four with most of the leaves at that depth and three of the leaves at depth two. At depths one, two, and three, the

-17-

significance information is the same as FIG. 7B. At depth four, the four sub-sub-quadrants of the lower left sub-quadrant from depth two are examined to determine if any of the entries are significant. In this case, $s^0(c_{4,2})$, the lower right sub-sub-quadrant of the lower left sub-quadrant, is now also significant. As a result, nodes 44, 54, 62, 66, and 72 are labeled with a one and nodes 46-52, 56-60, 64, 68, 70, and 74 are labeled with a zero. The final tree still has root node 26, branch nodes 28 and 36-42, and leaf nodes 44-74 and 30-34. As above, the values for bits b^0 for coefficients $c_{1,1}$, $c_{1,4}$, $c_{3,2}$, and $c_{4,3}$ have been noted under nodes 44, 54, 62, and 72, respectively, for future reference when coding the refinement information.

In FIG. 8C is depicted a table illustrating the encoding of the significance information and the refinement information for FIGS. 8A and 8B. Because below the highest bit-plane only the zero labeled nodes of the next higher tree are of interest, in this case, only nodes 46-52, 56-60, 64-70, 74, and 30-34 of FIG. 7B are of interest for coding significance information for FIG. 8B. Describing the significance information from left to right and in a bottom-up-depth-first fashion, nodes 46-52, 56-60, 64, 68, 70, 74, and 30-34 remain unchanged. Node 66 changes to being significant. The resulting order of the description is 46-52, 56-60, 64-70, 74, and 30-34. The resulting significance information Δ_0 is shown in the table. In this case, the values for bits b^0 for coefficients $c_{1,1}$, $c_{1,4}$, $c_{3,2}$, and $c_{4,3}$ make up refinement information R_0 as shown in the table. Accordingly, after encoding all of the bit-planes of the coefficients from FIG. 3, the SNR scalable bit-stream consists of $\Delta_3 R_3 \Delta_2 R_2 \Delta_1 R_1 \Delta_0 R_0$.

Although presented in the context of compression of image data, one of ordinary skill in the art will realize that the method described above will apply to any coding of the bit-planes of an array of numbers. In addition, such skilled persons will realize that the encoding of significance information Δ_n and refinement information R_n may be further compressed using Huffman coding or context based arithmetic coding. While the invention has been

[illegible]

CLAIMS

What is claimed is:

1. A method of coding the bit-planes of an array of numbers comprising the steps

2 of:

converting the values in the array of numbers to binary;

4 determining the number of bit-planes based on a number having the maximum
absolute value of the array of numbers;

6 generating a tree structured description of significance information for each bit-plane
of the array based on a modified quad-tree coding technique;

8 generating an SNR scalable encoding of the significance information for each bit-
plane by describing new branches and leaves of the tree corresponding to each bit-plane in a
10 bottom-up-depth-first manner;

generating an encoding of refinement information for each bit-plane; and

12 generating a SNR scalable description of the array by concatenating the encoding of
the significance information and the refinement information generated for each bit-plane.

2. The method according to claim 1 further comprising the step of truncating the

2 binary values to a predetermined level of accuracy after the step of converting.

3. A method of coding the bit-planes of an array of numbers, wherein the values

2 in the array of numbers have been converted to binary, the binary values have been truncated
to a predetermined level of accuracy, and the number of bit-planes has been determined based

-20-

4 on a number having the maximum absolute value of the array of numbers, the method comprising the steps of:

6 generating a tree structured description of significance information for each bit-plane of the array based on a modified quad-tree coding technique;

8 generating an SNR scalable encoding of the significance information for each bit-plane by describing new branches and leaves of the tree corresponding to each bit-plane in a bottom-up-depth-first manner;

generating an encoding of refinement information for each bit-plane; and

12 generating a SNR scalable description of the array by concatenating the encoding of the significance information and the refinement information generated for each bit-plane.

4. An apparatus for coding the bit-planes of an array of numbers comprising:

2 means for converting the values in the array of numbers to binary;

means for truncating the binary values to a predetermined level of accuracy;

4 means for determining the number of bit-planes based on a number having the maximum absolute value of the array of numbers;

6 means for generating a tree structured description of significance information for each bit-plane of the array based on a modified quad-tree coding technique;

8 means for generating an SNR scalable encoding of the significance information for each bit-plane by describing new branches and leaves of the tree corresponding to each bit-plane in a bottom-up-depth-first manner;

means for generating an encoding of refinement information for each bit-plane; and

-21-

12 means for generating a SNR scalable description of the array by concatenating the
encoding of the significance information and the refinement information generated for each
14 bit-plane.

5. The apparatus according to claim 4 further comprising means for truncating
2 the binary values to a predetermined level of accuracy.

6. A apparatus for coding the bit-planes of an array of numbers, wherein the
2 values in the array of numbers have been converted to binary, the binary values have been
truncated to a predetermined level of accuracy, and the number of bit-planes has been
4 determined based on a number having the maximum absolute value of the array of numbers,
the apparatus comprising:

6 means for generating a tree structured description of significance information for each
bit-plane of the array based on a modified quad-tree coding technique;

8 means for generating an SNR scalable encoding of the significance information for
each bit-plane by describing new branches and leaves of the tree corresponding to each bit-
10 plane in a bottom-up-depth-first manner;

means for generating an encoding of refinement information for each bit-plane; and

12 means for generating a SNR scalable description of the array by concatenating the
encoding of the significance information and the refinement information generated for each
14 bit-plane.

7. A computer coding system for an input image, the system having a sampling filter which decomposes the input image into four frequency subbands and outputs a Wavelet transform, the system comprising:

an encoder which generates a SNR scalable description of the Wavelet transform by concatenating an encoding of significance information and an encoding of refinement information generated for each bit-plane, wherein the encoding of the significance information for each bit-plane is generated by describing new branches and leaves of the tree corresponding to each bit-plane in a bottom-up-depth-first manner.

8. The system according to claim 7 further comprising a decoder which utilizes the SNR scalable description of the Wavelet transform to produce an output image.

-23-

APPARATUS FOR AND METHOD OF SNR SCALABLE QUAD-TREE BIT-PLANE CODING

ABSTRACT OF THE DISCLOSURE

5 An apparatus for and a method of coding the bit-planes of an array of numbers. The values in the array of numbers are converted to binary. The binary values are truncated to a predetermined level of accuracy. The number of bit-planes is determined based on the largest absolute value. A tree structured description of the array is generated based on a modified quad-tree coding technique. An SNR (signal to noise ratio) scalable encoding of the
10 significance information for each bit-plane is generated by describing new branches and leaves of the tree corresponding to each bit-plane in a bottom-up-depth-first manner. An encoding of refinement information for each bit-plane is generated. A SNR scalable description of the array is generated by concatenating the encoding of the significance information and the refinement information generated for each bit-plane.




FIG. 1




FIG. 2

$C_{i,j}$

	1	2	3	4	5	6	7	8
1	10	0	0	6	0	0	0	0
2	0	0	0	0	0	0	0	0
3	0	3	0	0	0	0	0	0
4	0	1	-9	0	0	0	0	0
5	0	0	0	0	0	0	0	0
6	0	0	0	0	0	0	0	0
7	0	0	0	0	0	0	0	0
8	0	0	0	0	0	0	0	0

FIG. 3

DECIMAL	BINARY				
	SGN	b^3	b^2	b^1	b^0
$C_{1,1} = 10$		1	0	1	0
$C_{1,4} = 6$		0	1	1	0
$C_{3,2} = 3$		0	0	1	1
$C_{4,2} = 1$		0	0	0	1
$C_{4,3} = -9$	-	1	0	0	1

FIG. 4

$S^3(c_{i,j})$

	1	2	3	4	5	6	7	8
1	1	0	0	0	0	0	0	0
2	0	0	0	0	0	0	0	0
3	0	0	0	0	0	0	0	0
4	0	0	1	0	0	0	0	0
5	0	0	0	0	0	0	0	0
6	0	0	0	0	0	0	0	0
7	0	0	0	0	0	0	0	0
8	0	0	0	0	0	0	0	0

FIG. 5A




FIG. 5B

$$\begin{array}{l} \Delta_3 \longrightarrow \quad 1 \quad 1 \quad 1 \quad 1 \quad [0] \quad 0 \quad 0 \quad 0 \quad 0 \quad 1 \quad 0 \quad 0 \quad 1 \quad [1] \quad 0 \quad 0 \quad 0 \quad 0 \\ R_3 \longrightarrow \quad n/a \end{array}$$

FIG. 5C

$S^2(c_{i,j})$

	1	2	3	4	5	6	7	8
1	1	0	0	1	0	0	0	0
2	0	0	0	0	0	0	0	0
3	0	0	0	0	0	0	0	0
4	0	0	1	0	0	0	0	0
5	0	0	0	0	0	0	0	0
6	0	0	0	0	0	0	0	0
7	0	0	0	0	0	0	0	0
8	0	0	0	0	0	0	0	0

FIG. 6A




FIG. 6B

$$\begin{array}{l} \Delta_2 \longrightarrow 0 \ 0 \ 0 \ 0 \ 0 \ 0 \ 0 \ 1 \ 0 \ 1 \ [0] \ 0 \ 0 \ 0 \ 0 \ 0 \\ R_2 \longrightarrow 0 \ 0 \end{array}$$

FIG. 6C

FIG. 7A

0000000000000000




FIG. 7B

$$\begin{array}{l} \Delta_1 \longrightarrow 0 \ 0 \ 0 \ 0 \ 0 \ 0 \ 0 \ 0 \ 0 \ 1 \ 0 \ 1 \ 0 \ 0 \ 0 \ 0 \ 0 \\ R_1 \longrightarrow 1 \ 1 \ 0 \end{array}$$

FIG. 7C

$S^0(c_{i,j})$

	1	2	3	4	5	6	7	8
1	1	0	0	1	0	0	0	0
2	0	0	0	0	0	0	0	0
3	0	1	0	0	0	0	0	0
4	0	1	1	0	0	0	0	0
5	0	0	0	0	0	0	0	0
6	0	0	0	0	0	0	0	0
7	0	0	0	0	0	0	0	0
8	0	0	0	0	0	0	0	0

FIG. 8A

004600 346400




FIG. 8B

$$\begin{array}{l} \Delta_0 \longrightarrow 0 \ 0 \ 0 \ 0 \ 0 \ 0 \ 0 \ 0 \ 1 \ [0] \ 0 \ 0 \ 0 \ 0 \ 0 \ 0 \\ R_0 \longrightarrow 0 \ 0 \ 1 \ 1 \end{array}$$

FIG. 8C

DECLARATION AND POWER OF ATTORNEY
FOR PATENT APPLICATIONATTORNEY DOCKET NO. 10990265-1

As a below named inventor, I hereby declare that:

My residence/post office address and citizenship are as stated below next to my name;

I believe I am the original, first and sole inventor (if only one name is listed below) or an original, first and joint inventor (if plural names are listed below) of the subject matter which is claimed and for which a patent is sought on the invention entitled:

APPARATUS FOR AND METHOD OF SNR SCALABLE QUAD-TREE BIT-PLANE CODING

the specification of which is attached hereto unless the following box is checked:

() was filed on _____ as US Application Serial No. or PCT International Application Number _____ and was amended on _____ (if applicable).

I hereby state that I have reviewed and understood the contents of the above-identified specification, including the claims, as amended by any amendment(s) referred to above. I acknowledge the duty to disclose all information which is material to patentability as defined in 37 CFR 1.56.

Foreign Application(s) and/or Claim of Foreign Priority

I hereby claim foreign priority benefits under Title 35, United States Code Section 119 of any foreign application(s) for patent or inventor(s) certificate listed below and have also identified below any foreign application for patent or inventor(s) certificate having a filing date before that of the application on which priority is claimed:

COUNTRY	APPLICATION NUMBER	DATE FILED	PRIORITY CLAIMED UNDER 35 U.S.C. 119
			YES: _____ NO: _____
			YES: _____ NO: _____

Provisional Application

I hereby claim the benefit under Title 35, United States Code Section 119(e) of any United States provisional application(s) listed below:

APPLICATION SERIAL NUMBER	FILING DATE

U. S. Priority Claim

I hereby claim the benefit under Title 35, United States Code, Section 120 of any United States application(s) listed below and, insofar as the subject matter of each of the claims of this application is not disclosed in the prior United States application in the manner provided by the first paragraph of Title 35, United States Code Section 112, I acknowledge the duty to disclose material information as defined in Title 37, Code of Federal Regulations, Section 1.56(a) which occurred between the filing date of the prior application and the national or PCT international filing date of this application:

APPLICATION SERIAL NUMBER	FILING DATE	STATUS (patented/pending/abandoned)

POWER OF ATTORNEY:

As a named inventor, I hereby appoint the following attorney(s) and/or agent(s) to prosecute this application and transact all business in the Patent and Trademark Office connected therewith:

Customer Number 022879Place Customer
Number Bar Code
Label here

See Attached Page 3 of 3

Send Correspondence to:
HEWLETT-PACKARD COMPANY
Intellectual Property Administration
P.O. Box 272400
Fort Collins, Colorado 80528-9599

Direct Telephone Calls To:

Marc P. Schuyler
(650) 857-3359

I hereby declare that all statements made herein of my own knowledge are true and that all statements made on information and belief are believed to be true; and further that these statements were made with the knowledge that willful false statements and the like so made are punishable by fine or imprisonment, or both, under Section 1001 of Title 18 of the United States Code and that such willful false statements may jeopardize the validity of the application or any patent issued thereon.

Full Name of Inventor: David Scott TaubmanCitizenship: AustraliaResidence: ~~1628 Bancroft Way, Berkeley, CA 94703 USA~~ 20 WINGATE AVE, EASTWOODPost Office Address: ~~1628 Bancroft Way, Berkeley, CA 94703 USA~~ NSW, 2122, AUSTRALIAInventor's Signature Date 12 MARCH, 00


**DECLARATION AND POWER OF ATTORNEY
FOR PATENT APPLICATION (continued)**

ATTORNEY DOCKET NO. 10990265-1

Full Name of # 2 joint inventor: Erik Ordentlich Citizenship: USA

Residence: 425 Grant Avenue #36, Palo Alto, CA 94306 USA

Post Office Address: 425 Grant Avenue #36, Palo Alto, CA 94306 USA

 Date 2/11/00

Full Name of # 3 joint inventor: _____ Citizenship: _____

Residence: _____

Post Office Address: _____

Inventor's Signature _____ Date _____

Full Name of # 4 joint inventor: _____ Citizenship: _____

Residence: _____

Post Office Address: _____

Inventor's Signature _____ Date _____

Full Name of # 5 joint inventor: _____ Citizenship: _____

Residence: _____

Post Office Address: _____

Inventor's Signature _____ Date _____

Full Name of # 6 joint inventor: _____ Citizenship: _____

Residence: _____

Post Office Address: _____

Inventor's Signature _____ Date _____

Full Name of # 7 joint inventor: _____ Citizenship: _____

Residence: _____

Post Office Address: _____

Inventor's Signature _____ Date _____

Full Name of # 8 joint inventor: _____ Citizenship: _____

Residence: _____

Post Office Address: _____

Inventor's Signature _____ Date _____

As a named inventor, I hereby appoint the following attorney(s) and/or agent(s) listed below to prosecute this application and transact all business in the Patent and Trademark Office connected therewith.

NAME	REGISTRATION NUMBER
Baker, Freling E.	24,078
Maxham, Lawrence A.	24,483
Martínez, Peter R.	42,845
Robbins, Steven J.	40,299
Woycechowsky, David B.	39,079

	1970	1971	1972	1973	1974	1975	1976	1977	1978	1979	1980	1981	1982	1983	1984	1985	1986	1987	1988	1989	1990	1991	1992	1993	1994	1995	1996	1997	1998	1999	2000	2001	2002	2003	2004	2005	2006	2007	2008	2009	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022	2023	2024	2025	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	2036	2037	2038	2039	2040	2041	2042	2043	2044	2045	2046	2047	2048	2049	2050	2051	2052	2053	2054	2055	2056	2057	2058	2059	2060	2061	2062	2063	2064	2065	2066	2067	2068	2069	2070	2071	2072	2073	2074	2075	2076	2077	2078	2079	2080	2081	2082	2083	2084	2085	2086	2087	2088	2089	2090	2091	2092	2093	2094	2095	2096	2097	2098	2099	2100	2101	2102	2103	2104	2105	2106	2107	2108	2109	2110	2111	2112	2113	2114	2115	2116	2117	2118	2119	2120	2121	2122	2123	2124	2125	2126	2127	2128	2129	2130	2131	2132	2133	2134	2135	2136	2137	2138	2139	2140	2141	2142	2143	2144	2145	2146	2147	2148	2149	2150	2151	2152	2153	2154	2155	2156	2157	2158	2159	2160	2161	2162	2163	2164	2165	2166	2167	2168	2169	2170	2171	2172	2173	2174	2175	2176	2177	2178	2179	2180	2181	2182	2183	2184	2185	2186	2187	2188	2189	2190	2191	2192	2193	2194	2195	2196	2197	2198	2199	2200	2201	2202	2203	2204	2205	2206	2207	2208	2209	2210	2211	2212	2213	2214	2215	2216	2217	2218	2219	2220	2221	2222	2223	2224	2225	2226	2227	2228	2229	2230	2231	2232	2233	2234	2235	2236	2237	2238	2239	2240	2241	2242	2243	2244	2245	2246	2247	2248	2249	2250	2251	2252	2253	2254	2255	2256	2257	2258	2259	2260	2261	2262	2263	2264	2265	2266	2267	2268	2269	2270	2271	2272	2273	2274	2275	2276	2277	2278	2279	2280	2281	2282	2283	2284	2285	2286	2287	2288	2289	2290	2291	2292	2293	2294	2295	2296	2297	2298	2299	2300	2301	2302	2303	2304	2305	2306	2307	2308	2309	2310	2311	2312	2313	2314	2315	2316	2317	2318	2319	2320	2321	2322	2323	2324	2325	2326	2327	2328	2329	2330	2331	2332	2333	2334	2335	2336	2337	2338	2339	2340	2341	2342	2343	2344	2345	2346	2347	2348	2349	2350	2351	2352	2353	2354	2355	2356	2357	2358	2359	2360	2361	2362	2363	2364	2365	2366	2367	2368	2369	2370	2371	2372	2373	2374	2375	2376	2377	2378	2379	2380	2381	2382	2383	2384	2385	2386	2387	2388	2389	2390	2391	2392	2393	2394	2395	2396	2397	2398	2399	2400	2401	2402	2403	2404	2405	2406	2407	2408	2409	2410	2411	2412	2413	2414	2415	2416	2417	2418	2419	2420	2421	2422	2
--	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	---